AMP Electrical Services

330 W 1st St
Oswego, NY 13126-3624 USA
AMPcny@gmail.com

Estimate

ADDRESS
New Haven Town Hall
4279 NY-104
New Haven NY 13114

ESTIMATE 1198
DATE 11/04/2026

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	16 Electrical & Lighting	Installation of new panel board located adjacent to existing conduits where building was demolished. Panel board to be made of solid pressure treated materials including 4x4 PT posts- and 2x8 PT boards for panel mounting location. Installation of new 100 amp exterior rated electrical panel with exterior rated GFCI. Modification of existing conduits and conductors to feed into new panel to be re-energized and labeled on appropriate breakers etc.	1	2,950.00	2,950.00
	electrical inspection fees	Third Party Electrical inspections fees required by local codes.	1	300.00	300.00

SUBTOTAL	3,250.00
TAX	0.00
TOTAL	**$3,250.00**

Accepted By

Accepted Date

Fisk Electric LLC
1423 N Salina St
Syracuse, NY 13208-1522
US
+13154020291
jack@fiskelectricinc.com

Estimate

ADDRESS
New Haven Town Barn
4279 NY-104
Oswego, NY

SHIP TO
New Haven Town Barn
4279 NY-104
Oswego, NY

ESTIMATE # 3028
DATE 10/29/2026

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	Service Department	Pedestal -build pedestal out of dimensional pressure treated lumber -furnish and install 100a 3R weather rated panel -rework existing conduits and feeders into new panel -furnish and install photo eye to control flag and street lights Fisk is responsible for all labor, materials and clean up	1	2,500.00	2,500.00

We accept credit cards, PayPal, Venmo, ACH & Checks.

MAIL CHECKS TO:
1423 N. Salina St
Syracuse, NY 13208

Thank you for your business!
50% payment due on acceptance of estimate, remaining 50% due at service completion.

Paying via ACH/Check? YOUR TOTAL:

SUBTOTAL	2,500.00
TAX	0.00
TOTAL	**$2,500.00**

Accepted By

Accepted Date

SCRIBA ELECTRIC INC.

www.scribaelectric.com | ed@scribaelectric.com
Phone: 315-342-7681 | Fax: 315-342-7682

Town of New Haven- Outdoor Panel

INSTALLATION PROPOSAL

Owner: Town of New Haven

Attention: Jen Woolson- Town Clerk

Date: October 29, 2026

Scriba Electric Inc. proposes to furnish labor, materials, and equipment to install a new outdoor panel and complete the associated work described below.

Scope of Work

- Install one new 100-amp, single-phase, outdoor-rated panel with main breaker. (match feed breaker)
- Provide and install a freestanding panel mounting stand.
- Provide and install two protective bollards with concrete anchoring.
- Provide and install branch circuit breakers for the agreed existing circuits.
- Install one weather-resistant GFCI duplex receptacle with weatherproof box and in-use cover.
- Trench approximately 20 feet from the existing underground wiring to the new panel location. Transfer and reconnect existing feeder and branch circuit wiring, subject to verification of conductor size, condition, and adequate length.
- Complete associated conduit connections, grounding, bonding, circuit identification, and operational testing.

Clarifications: Proposal is based on reuse of existing underground wiring and raceways and includes approximately 20 feet of trenching. Replacement or extension of unsuitable existing wiring, new underground feeders, additional trenching, pavement restoration, and permit or inspection fees are excluded unless added by written authorization. Breaker sizes and quantities shall be confirmed before installation.

Flag pole Light & road way Light repair not included – Scriba assumes they work.

Total Proposed Price: $ 3,750.00 no tax

Additional work outside this scope requires written authorization.

Accepted by: _____ Date: _____

Title: _____